

**CITY OF CYPRESS  
BUILDING DIVISION**

**SLAB REPLACEMENT REQUIREMENTS**

- 4" slab
- sand bed – min. 2" on top of 10 mill visqueen
- 6-6-10-10 wire welded mesh or #3 @ 12 " o.c. or #4 @ 18" o.c.
- inspection prior to pour of concrete
- Type V cement must be used
- turn in mix ticket